

**Society for Applied Microwave Electronics Engineering & Research
(SAMEER)**

**(R & D Laboratory of Ministry of Electronics & Information Technology, Govt. of India)
Plot-L2, Block-GP, Sec-V, Salt Lake Electronics Complex, Kolkata-700091**



TENDER DOCUMENT

Name of work : “Repair and Renovation of Non Residential Building at Salt Lake Sec-V office building of “SAMEER Kolkata Centre” located at Plot-L2, Block-GP, Sec-V, Salt Lake Electronics Complex, Kolkata-700091, West Bengal”

Ph : 091-33-2357-4875 / 2357-4894 Fax : 091-33-2357-4950, E-mail : purchase@mmw.sameer.gov.in / vivek.sameer@gov.in

NOTICE INVITING TENDER(NIT)

NIT Ref No. SMR (K)/CIVIL/REP/SEC-V/2023-24

Dated: 17th November, 2023

Office-In-Charge of SAMEER Kolkata invites sealed tender (Two bid system) from the experienced and resourceful civil contractor for execution of the following repair and renovation work:

NAME OF WORK: "Repair and Renovation of Non-Residential Building at Salt Lake Sec-V office building of "SAMEER Kolkata Centre" located at Plot-L2, Block-GP, Sec-V, Salt Lake Electronics Complex, Kolkata-700091, West Bengal"

Site of Work: SAMEER Kolkata Centre, Plot-L2, Block GP, Sec-V, Salt Lake Electronics complex, Kolkata - 700091

Estimated Cost: Rs 29, 79,180 /- (Rupees Twenty-Nine Lakhs Seventy-Nine Thousand One Hundred Eight only)

Tender Fees: Rs. 500 /- (Rupees Five Hundred Only)

Earnest Money (EMD): Rs. 89,375.00 (Rupees Eighty-Nine Thousand Three-Hundred Seventy-Five Only)

Date of publication : 17th November, 2023

Last date for submission of Tender/ Bid : 7th Dec, 2023 up to 5.00 P.M


Pre-bid Meeting : 28th Nov, 2023 at 11.00 A.M

Start date for submission of tender : 30th November, 2023

Date & time of opening of Technical Bid : 11th Dec, 2023 at 11.A.M

Date & Time of opening of financial bid : will be intimated

For uploading tender document, please go to website: kolkata.sameer.gov.in / www.eprocure.gov.in. All updates/corrigendum/amendment will be uploaded at these sites only.


Vivek Kumar Singh
Head, A & AO
email : purchase@mmw.sameer.gov.in

INDEX

S.No.	CONTENTS	PAGE No.
TECHNICAL BID :-		
1	Sec-I : General Instruction	5-7
2	Sec-II : Scope of Work	8
3	Sec-III : Terms & Conditions	9-15
FINANCIAL BID :-		
4	Sec-IV: Schedule of Quantities	16
5	Sec-V: Technical Specifications	17-21
6	Form of Tender	22

**SOCIETY FOR APPLIED MICROWAVE ELECTRONICS ENGINEERING &
RESEARCH (SAMEER), KOLKATA, WEST BENGAL**

Repair and Renovation of Non-Residential Building at Salt Lake Sec-V office building of “SAMEER Kolkata Centre” located at Plot-L2, Block-GP, Sec-V, Salt Lake Electronics Complex, Kolkata-700091, West Bengal”

PART -I: TECHNICAL BID

**TENDER REF NO. : SMR (K)/CIVIL/REP/SEC-V/2023-24
Dated 17th Nov, 2023**

SEC-I: GENERAL INSTRUCTION

INTRODUCTION:

Society for Applied Microwave Electronics Engineering & Research (SAMEER) is a premier R & D institute of Ministry of Electronics & Information Technology, Govt. Of India. SAMEER invites sealed two parts tenders from the reputed firm/contractor for renovation and repair works on its own office building located at Plot-L2, Block-GP, Sec-V, Salt Lake Electronics Complex, Kolkata-700091.

- i. All the interested parties are advised to go through this tender document carefully and inspect the office building to have the adequate idea / information about the work before submission of tender. Contractors are requested to contact our concerned person Shri Sourav Sarkar (033-2357-4875/4894) / (Monday to Friday) between 10.00 A.M to 5.00 P.M before visit to SAMEER Kolkata.
- ii. The tender should be submitted in two-part bid system i.e., Technical Bid and Financial Bid.
- iii. Both Technical and Financial Bid should be submitted in two separate sealed envelopes superscribed as Technical Bid and Financial Bid with Tender Ref No. These two sealed separate envelopes should be put in a third sealed envelope and should be superscribed as “Tender for **“Repair and Renovation of Non-Residential Building at Salt Lake Sec-V office building of “SAMEER Kolkata Centre” located at Plot-L2, Block-GP, Sec-V, Salt Lake Electronics Complex, Kolkata-700091, West Bengal”**

EARNEST MONEY DEPOSIT (EMD): Rs. Rs. 89,375.00 (Rupees Eighty-Nine Thousand Three-Hundred Seventy-Five Only) to be deposited along with Technical Bid by crossed demand draft / banker’s cheque favouring SAMEER Kolkata Centre payable at Kolkata. Please note that bid received without EMD will not be considered and will be summarily rejected. The EMD will be refunded to the unsuccessful bidders immediately after finalization of the contract. EMD for successful bidder will be converted as Performance Security Deposit on acceptance of the bid. No interest will be paid on the EMD.

- iv. **COST OF TENDER:** Tender fee of Rs. 500.00 (Non-refundable) by crossed demand draft / banker’s cheque favouring SAMEER Kolkata Centre payable at Kolkata shall be deposited along with Technical **Bid**, if tender document is downloaded from website. Tender document can also be collected from office on all working days (Mon to Friday from 10AM to 4 P.M) by making payment of tender fee in cash. Copy of the Money receipt should be submitted along with technical bid. Please note that bid received without tender fee will not be considered and will be summarily rejected.

- v. **TECHNICAL BID** should contain EMD, Tender fee, relevant documents in support of eligibility criteria, Terms and conditions with authorized sign and seal as a token of acceptance laid down in the tender document and work programme schedule.

vi. **FINANCIAL BID:** The tenderer shall quote for all the items as per schedule of quantities of Financial Bid, failing which the bid shall be considered non responsive, incomplete and will be summarily rejected. Rates for the items shall be quoted in the Financial Bid of this tender and the amount for each item should be worked out and requisite totals be given. Special care should be taken to write the rates in figures as well as in words. In case of any dispute, rates appearing in words shall be treated final.

vii. **BID PRICE:** The Rate should be the total composite price inclusive of cost of manpower, material, freight, loading, unloading, taxes, duties, cess, levies, insurance etc. excluding GST. GST should be reflected as per format mentioned in Financial Bid. No escalation of whatsoever nature, shall be payable in future due to any revision amendment in any act/ statute governing this contract. SAMEER will not entertain any claim whatsoever in respect of the same. The rate(s) must be quoted in decimal coinage. Amounts must be quoted in full rupees by ignoring fifty paise and less and considering more than fifty paise as rupee one.

viii. **DISCOUNT:** if any, offered by the bidders **shall not be considered** at the time of evaluation of Financial Bid by the evaluation committee. Bidders desiring to offer any discount shall therefore consider while preparing bid and shall quote clearly net price taking all such factors like discount, free supply etc.

ix. **ELIGIBILITY CRITERIA:**

The tenderer should have and submit relevant documents along with Technical Bid for participation in this tender as per below:

- a) Copy of valid registration certificate with local authorities/professional bodies/ CPWD/PWD (states)/MES/Railways/BRO/any other appropriate Govt. Body as civil contractor in appropriate class and categories should be submitted.
- b) Valid registration copies of PAN, TAN, TIN, GST, ESI, EPF.
- d) Copy of Labour license under the contract labour issued by appropriate Govt. as per Labour Act
- e) Copy of certificate of incorporation/registration of firm certificate/memorandum of Articles of Association Partnership deed Proprietorship deed/Declaration of proprietorship etc in support of legal entity of the tenderer as the case may be demanded by SAMEER and if required, the same shall be produced by tenderers.
- f) Copy of Income Tax return for the last three financial years 2020-21, 2021-22, and 2022-23
- g) **EXPERIENCE:** Contractor should have at least the following working experience with **Central Govt. /State Govt/ Autonomous govt. bodies/PSU** during the last 7 years as on 16th November, 2023. In support of experience **Work Order / agreement with completion certificate** must be submitted along with technical bid:
 - Three similar completed works costing not less than the amount of each Rs. 12.00 (Twelve) lakhs
 - OR two similar works not less than the amount of each Rs. 18.00 (Eighteen) Lakhs

- OR one similar completed work costing not less than Rs.24.00 (Twenty-Four) Lakhs

(Note: Similar works means construction work in civil / Repair and maintenance work in the field of civil/renovation work in civil)

The above experience should be provided in the following format:

Srl no.	Worked with the following organizations (mention the name of organization)	Value of the Work Order/Contract
1		
2		

h) Average annual financial turn over for the last 3 years ending 31st March of the previous financial year should be equal or more than Rs. 100.00 (One hundred) lakhs. Audited balance sheet for the last three years should be attached.

I) Copy of any other registration, which is mandatory for such agencies stipulated by concerned authorities from time to time.

j) A statement of up-to-date payment details of ESIC and EPF should be submitted

k) **BLACK LIST:** Bidder should submit declaration in the form of notarized affidavit on non-judicial stamp paper that he is not blacklisted by local authorities/professional bodies CPWD/PWD (states)/MES/Railways/BRO/competent local authorities / professional bodies any other statutory bodies fully / partly governed by the Government

x. **PERFORMANCE SECURITY DEPOSIT:** The successful bidder (whose tender is accepted after finalization of financial bid for issuing Work Order) will furnish performance security for the fulfilment of contract, an amount equal to 5 % of the value of the Work Order.

xi. **EVALUATION OF BIDS:** The technical bid will be scrutinized by the Technical Evaluation Committee as constituted by SAMEER to check all the requisite and relevant documents and their authenticity at the stipulated date and time. Necessary clarification on technical bid will be sought by email/ hard copy in the agency's letter head as the case may be. After evaluation, the technically qualified bidders will be informed about the date and time of opening the financial bids. Bidders may choose to be present in the opening of the Technical and financial bid meeting. Maximum two authorized persons will be allowed in the bid opening meeting. Upon evaluation of the offers the notification on award of contract will be intimated to the successful tenderer.

For any clarification, if required, please email at "purchase@mmw.sameer.gov.in / vivek.sameer@mmw.sameer.gov.in" / Ph: 033-2357-4875 / 4894

xii. **PREBID MEETING:** The Bidder(s) or his authorized official representatives are invited to attend a pre-bid meeting on date, time and venue specified as below:

Date: 28th November, 2023

Time: 11.00 A.M

Venue: Conference hall of SAMEER Kolkata Centre Plot L2, Block-GP, Sector-V Salt Lake Kolkata : 700091

SEC-II: SCOPE OF WORK

- i. The scope of work includes civil maintenance/renovation/upgrade work of the Sec-V office building of SAMEER Kolkata as per schedule of quantity.
 - ii. For timely completion of the work the bidder/contractor must have to deploy all tools & tackles, plants, machineries, equipment and materials required to perform the work simultaneously.
 - iii. The agency should ensure all safety precautions while execution of the repair and renovation work.
 - iv. The agency should ensure necessary labour license issued by appropriate Govt. for the execution of the work. Copy of documents relating thereto will be produced to SAMEER on demand.
 - v. Agency will maintain manpower muster roll and wage register
 - vi. The contractor will provide site supervisor/Civil Engineer at site. Site supervisor/ civil engineer should have adequate knowledge in civil work.
 - vii. Any other additional work apart of schedule of quantity, if required, will be executed after consultation with authorized person of SAMEER.
 - viii. All temporary arrangements, staging, working platforms, safety arrangements etc. is to be provided to carry out the work at their own cost.
-

SEC-III: TERMS AND CONDITIONS

1. DEFINITION OF TERMS:

CONTRACTOR: The Contractor shall mean the Bidder who will be awarded with the contract by SAMEER and shall include the contractor's executors, administrators, successors and permitted assignees.

SUB-CONTRACTOR : The 'Sub-Contractor' shall mean the person named in the Contract for any part of the works or any person to whom any part of the contract has been sublet by the contractor with the consent in writing of Officer-In-Charge of SAMEER and will include the legal representatives, successors and permitted assigns of such persons.

Equipment/materials shall mean and include all type of construction equipment & materials etc. required for true and satisfactory completion of the work under this contract.

2. **AUTHORISED PERSON OF SAMEER :** shall mean person / engineer engaged by SAMEER for the tender work

3. The repair and renovation work shall be carried out following CPWD norms and specifications. Whenever, the same are not available, Engineering practice as directed by Engineer, engaged by SAMEER shall be followed.

4. **VALIDITY OF BID:** The bid should be valid for **120 days** from the due date of the tender.

5. **COMPLETION OF WORK:** Time is very essential for this work. The work should be completed within **3 MONTHS** from the date of issue of the Work Order. However, contractors are required to complete the job at least 80% of the schedule of quantity **within 2 months**.

6. All the documents and photocopies submitted by tenderer /bidder should be attested, legible, signed and stamped by authorized signatory, otherwise the bid is likely to be rejected.

7. **PERFORMANCE SECURITY DEPOSIT:** The successful bidder (whose tender is accepted after finalization of financial bid for issuing Work Order) will furnish performance security an amount equal to 5% of the value of the Work Order. Earnest Money deposit (EMD) on acceptance of Tender shall be converted as a part of the performance security. Balance amount of performance security shall be realized from the RA Bill. It will be released after satisfactory expiry of Defective Liability period of 6 month after completion of the whole work on written request by the contractor and no interest shall be paid on performance security.

8. **FORFEITURE OF PERFORMANCE SECURITY DEPOSIT:** Performance security will be forfeited If any amount which is payable by the contractor is required to recover on account of any clause arising out of /contravening the Work Order/Contract.

9. **FORFEITURE OF EMD :** Earnest money shall be forfeited in case of following :

- If during the period of validity, the bidder withdraws/modifies its bid as a whole or in part.
- If the bidder deviates from any clarification/confirmation given by him subsequent to submission of his bid
- In case of successful bidder, if the Bidder fails to accept Work Order unconditionally

10. ARITHMETICAL ERROR: Arithmetical errors shall be rectified on the following basis: If there is any discrepancy between the unit price and total price that is obtained by multiplying the unit price and quantity, the unit price shall prevail and the total price shall be corrected by the purchaser. If there is a discrepancy between words and figures, the amount in words shall prevail. If the supplier does not accept the correction of the errors, his bid shall be stand rejected.

11. MEASUREMENTS AND TERMS OF PAYMENT: All items of work carried out by the contractor in accordance with the provision of the order having a financial value shall be entered in the computerised measurement book (CMB)/ log book etc. as per CPWD format so that a complete record is obtained of all works performed under the order and the value of work can be ascertained and determined there from. Measurement shall be taken jointly and every measurement thus taken shall be signed and dated by both the parties.

Payment will be made as per actual measurement of items works after completion of work. Bill should be generated on the required format and payment shall be released **within ten days** of its submission if all formalities as per terms of the contract are maintained.

However, payment of final bill shall be released after submission of completion certificate of the job, verification of overdue/overpayment if any and fulfilment of all contractual obligations by the contractor.

12. PAYMENT OF NON-SCHEDULED ITEMS: Payment will be made for various items as per existing CPWD/ PWD (state) rate. If not available in CPWD/ PWD payment will be made based on prevailing market rate with submission of rate analysis and admitted by SAMEER before execution of work.

13. OVERPAYMENT: SAMEER reserves the right to recover/ enforce recovery of any overpayments detected after payment as a result of post-payment audit or technical examination or by any other means, notwithstanding the fact that the amount of disputed item, if any, of the contractor exceeds the amount of such overpayments and irrespective of the fact whether such disputed claims of the contractor are subject matter of arbitration or not. The amount of such overpayment may be recovered from subsequent bill / security deposit

14. EXTENSION OF TIME: If the work is suspended due to reasons beyond the control of the contractor, the contractor shall immediately give notice in writing within 7(seven) days to SAMEER for each occasion. On receipt of such notice, SAMEER may verify the matter and agree to extend the completion period as may be reasonable but without prejudice to other terms and conditions of the contract as the case may be if the reasons behind the suspension of work are found to be justified.

15. LIQUIDATED DAMAGES: If the contractor fails to complete the work successfully within the time specified in the contract or any extension thereof, SAMEER shall recover from the contractor as liquidated damages a sum of half percent (0.5%) of the contract value of works for each calendar week of delay or part thereof. Delay relating to Force majeure clause is not applicable for recovery.

The total recovery against liquidated damage shall not exceed ten percent (10%) of the contract value of the work. An extension of time without imposition of liquidated damage, may be granted by SAMEER for delay in execution of work provided there is no fault whatsoever on the part of the contractor. Such extension may only be granted on the basis of application to be submitted by the contractor who has to establish that the extension of time required by him was not due to his fault.

16. ACCEPTANCE OF THE ORDER: The successful bidder has to submit acceptance of the order within 5 days from the date of issue of the order.

17. WORK PROGRAMME SCHEDULE: A chart with time schedule of the work should be **submitted along with Technical Bid.**

18. VARIATION, OMISSION, ADDITION & ALTERATION: The Contractor shall not modify the work until and unless approved by SAMEER in writing. The quantities provided in the Schedule of work are provisional only, which may vary up to any extent or may be deleted altogether. The quoted rate of each item shall remain firm till completion of contract. **SAMEER reserves the right to alter, amend, and omit or otherwise vary** the quantities as may be necessary. Payment shall be made as per actual execution.

19. MINOR WORK: For any additional minor work if required to be done beyond the schedule of works specified in this tender, separate order will be issued and payment for the same will be made as per existing CPWD rate. If not available in CPWD payment will be made based on prevailing market rate with submission of rate analysis and admitted by SAMEER.

20. MATERIAL: Material should be used for repair and renovation work as per technical specifications specified in Sec-V. For other material not containing in the specifications will be as per relevant ISI standard and good quality subject to prior approval of SAMEER. The material shall be in original packing clearly indicating manufacturing date, expiry date & price etc. Any item found defective / kind specified in the contract and/ or is unfit for work should be replaced free of cost to the satisfaction of SAMEER authority.

21. Cement used for the work should not be older than Two month from the date of manufacture. The contractor should purchase the cement from authorised dealer and submit the test certificates/vouchers prior to execution of the work.

22. Electricity and water for execution of the work will be supplied by SAMEER; the charges shall be borne by the contractor at the **rate of 0.5%** on the executed value. The contractor has to make his own arrangement for use of the same including extending temporarily lines etc. The contractor cannot claim any compensation for any failure in such supply caused due to any reason whatsoever in case of non-availability of electricity and water for construction purpose from SAMEER. The contractor will have to arrange for the same at his own cost.

23. HOLIDAY WORK: If the work is required to be carried out in two shifts and/or in Sundays & Holidays, prior written permission from SAMEER shall have to be obtained.

24. Canvassing whether directly or indirectly, in connection with tenders is strictly prohibited and the tenders submitted by the contractors who resort to canvassing will be liable to rejection. Tender received by email / fax will not be considered.

25. Tender must be submitted within due date. Tender received beyond the due date by any other means like postal delay etc. will not be considered.

26. SUB-LETTING OF CONTRACT: The contractor shall not, without the written consent of SAMEER, assign or sublet any part of the contract, other than for raw materials or for any part of the work provided that any such consent shall not relieve the contractor from any obligation, duty or responsibility under the contract. In the event of sub-letting any part of the contract is permitted, the fact that such permission has been accorded shall not establish any contractual relationship between the approved Sub- vendor and SAMEER of any of his liabilities and obligations under the contract.

27. The Rates quoted by the tenderer must hold good till the completion of work and shall not be subjected to escalation due to increase in local market rates of materials and labour. No claim on this account whatsoever shall be entertained at any stage including the extended period, if any.

28. FORCE MAJEURE: The Contractor shall not be liable to pay any liquidated damage for delay/failure to perform the contract for reasons of force majeure such as acts of God, acts of the public enemy, acts of Governments, fire, flood, epidemics, quarantine restriction, strikes, freight embargos and provided that the contractor shall within 7(seven) days from the beginning of such delay notify SAMEER in writing of the cause of delay. SAMEER shall verify the facts and grant such extension as found to be justified without imposing liquidated damage. The department shall not be responsible or liable to pay any compensation for any interruption in your work at the site due to strike, lockout, riot earthquake, flood, cyclone or civil commotion

or any other force of accident due to any reason beyond control. SAMEER shall not be held responsible to or liable to pay for any interruption in your work at the site arising out of resistance from the local public due to any resistance towards work.

29. DEFECT LIABILITY PERIOD: The term 'defect liability period' shall mean the period of Six (6) Calendar months from the certified date of its completion of whole work. If any defect is found within the defect liability period the contractor shall be liable to rectify/replace the materials at their own cost and responsibility. In case any defect of work is detected by the controlling officer within the period of six months, the defect liability period shall continue beyond six months. Defects/rectification work so notified shall have to be attended and completed satisfactorily within the specified date or as deemed fit by SAMEER. For faithful & due fulfilment of all obligations, this defect liability period shall be covered by Performance Security Deposit submitted by the contractor.

30. The contractor shall have to attend the local bodies like Municipality/ Police/CPWD/Labour officer and all other Government authorities to fulfil all the requirements to execute the order

31. REMOVAL OF PERSON EMPLOYED AT SITE: SAMEER shall be at liberty to ask the contractor to remove from the site any person, employed by the contractor in the execution of work, for misconducts, in competent or negligent in the proper performance of his duties and such persons shall not be again employed upon the work without the permission of SAMEER.

32. SAMEER will be at liberty to take samples during the course of execution of work, if necessary and get the same tested to ascertain the quality conforming to relevant specifications. The cost of sample and the charges for the testing will have to be borne by the contractor.

33. Irrespective of rates quoted by the bidder, the contractor shall be solely responsible for payment of Minimum Wages as stipulated by the Government from time to time.

34. The contractor will take utmost care to prevent from any damage to the property of SAMEER while execution of work. If any damage arise apart from repair of maintenance work will be rectified by contractor at his own cost to the satisfaction of SAMEER.

35. AWARD OF WORK: SAMEER will not be bound to accept the lowest tender and reserves the right to accept or reject any or all the tenders received and to place order to one or more firms without assigning any reason thereof. The notification of award of contract will be made in writing to the best responsive bidder who is technically suitable and financially acceptable after evaluation of financial bid.

36. As the work will have to be carried out in building and area in use the contractor shall ensure a) That the normal functioning of Employer is not affected as far as possible b) That the work is carried out in an orderly manner without noise and obstruction to flow of traffic. C) Contractor will arrange photo identity card for his workers with approval of SAMEER.

37. Safety Measures: The contractor shall ensure safety of his workers, others at site of work and shall be responsible for any consequence arising out of execution of the Repair and Maintenance work. The contractor shall obtain valid license issued by appropriate Govt to comply with the provisions as per the contract labour to execute the work.

Workmen's Compensation for accident or injury to any workman: SAMEER shall not be liable for damages or compensation payable as per provision of law in respect or consequence of any **accident or injury** to any workmen or other person in the employment of the contractor. The contractor shall have to pay all claims, demands, preceding costs, charges and expenses whatsoever in respect thereof or in relation thereto. **Insurance policy** covering as per provisions of Workmen's compensation act for all the workmen to be engaged by the contractor is to be made by him.

Apart from the above workmen compensation for workers, third party insurance will also be made. Copy of the documents relating to the above effect should be produced to SAMEER on demand.

38. CLEARING SITE ON COMPLETION: On Completion of the work the contractor shall clear away and remove from the site all constructional plant, surplus materials, rubbish and temporary work of every kind and leave the whole of the site and work clean and in good and tidy condition to the satisfaction of SAMEER.

39. TERMINATION OF WORK ORDER: If the contractor neglects or fail to proceed with the work proportionate to the scheduled time of completion or fails to complete the work within scheduled time of completion or within extended time approved by SAMEER and SAMEER shall have right to terminate the order/contract after giving notice in writing to the contractor. If the contractor fails, after 14 (fourteen) days of such notice, to proceed with the work in the manner notified, SAMEER shall terminate the contract and call the contractor to take joint measurement along with the Engineer for finished portion of work. If the Contractor does not appear for a joint measurement, measurement taken by SAMEER will be taken as final and bound. In that case, SAMEER shall take possession of the work site and may engage other agency to complete the work. Extra cost, if incurred to get the unfinished work done through other agency, will be realized from him, from his pending bills or performance security deposit or both as case may be. If the contract is terminated as above, the contractor shall have no claim for compensation against SAMEER for any loss or deterioration of any materials that he may have collected or engaged or entered into on account of the work.

40. SETTLEMENT OF DISPUTES: All disputes concerning question of act arising under the contract shall be decided by SAMEER on receipt of written appeal by the contractor. Any dispute or differences arising out of or in connection with this contract shall to the extent possible be settled amicably and where settlement cannot be reached then such disputes shall be subject to settlement under the jurisdiction of Calcutta High Court.

41. SAMEER reserves the right to accept or reject any tender or all tenders or part of tender without assigning any reason whatsoever.

-----XX-----

**SOCIETY FOR APPLIED MICROWAVE ELECTRONICS ENGINEERING &
RESEARCH (SAMEER), KOLKATA, WEST BENGAL**

Name of work: “Repair and Renovation of Non-Residential Building at Salt Lake Sec-V office building of “SAMEER Kolkata Centre” located at Plot-L2, Block-GP, Sec-V, Salt Lake Electronics Complex, Kolkata-700091, West Bengal”

PART -II: FINANCIAL BID

TENDER REF NO. : SMR (K)/CIVIL/REP/SEC-V/2023-24 Dated: 17th November, 2023

SEC-IV: SCHEDULE OF QUANTITIES

Schedule of quantities please see the Annexure attached:

SEC-V: TECHNICAL SPECIFICATIONS (REPAIR AND RENOVATION WORKS)

APPROVED MAKE LIST OF MATERIALS TO BE USED WHEREVER APPLICABLE

1) General

Specifications, scope of work, schedule of rates and drawings for a particular tender shall be read in conjunction with each other. In case of conflicts/contradictions amongst them, the clarification shall be obtained from SAMEER whose decision, shall be final & binding. Following procedure shall be followed for the necessary clarification.

- A. Item description shall prevail over specifications for item rates when provisions therein are different from those in specifications. Whenever any requirement is not covered in item description but is conversed in specifications, the specifications shall be followed in addition to the requirements of item description; no extra payment shall be made to the contractor for executing such item as per specification.
- B. Whenever drawing call for requirements different from or additional to those in item description and specification, the decision of SAMEER shall be obtained. However, no extra payment shall be made to the contractor for executing any work incorporating requirements additional to those in item description and specification but covered in applicable drawings or standards. Wherever references have been made to Indian standard or any other specifications the same shall mean to refer to the latest specifications irrespective of any particular edition of such specifications being mentioned in the specifications below in schedule of quantities.

2) WORKMANSHIP

Workmanship shall be to the satisfaction of SAMEER, the contractor shall follow the specification, relevant codes & manufacturer's guidelines for achieving desired level of workmanship as per specification & good engineering practice, any executed work not conforming to the specification or not to the satisfaction of SAMEER shall be rectified by the contractor as directed by SAMEER, no extra payment shall be made to the contractor for such rectification.

3) MEASUREMENT

Mode of measurement is generally specified in each specification, whenever mode of measurement is not specified, relevant IS- code, shall be applicable.

4) MATERIALS

- (a) All materials shall be best of their kind and shall conform to the latest Indian standard
- (b) All materials shall be of approved quality as per samples and from origins approved by SAMEER before ordering & procurement. The contractor shall furnish necessary certificates further to that he shall get the materials tested from approved test house if asked by SAMEER & submit the test certificate at his own cost for which no extra payment shall be made to him. SAMEER shall have the right to reject all or any of the materials intended to be used and such materials shall be immediately removed from the site by the contractor at his own cost without any claim for Compensation etc. due to such rejection.

- (c) A set of specimen samples of all approved materials shall be kept at site with all precautionary measure, cost of which to be borne by the contractor.

5) CEMENT

Unless otherwise specifically called for, cement for RCC and PCC / lean concrete works shall be one the following. The type of cement selected shall be appropriate for the intended use.

Portland slag cement.	IS:455
Portland puzzling cement (fly ash based)	IS:1489(part-1)

PREFERABLE BRAND NAME OF CEMENT COMPANEY -
ACC/ULTRATECH/LAFARGE/AMBUJA

Cement shall be stored on pucca go down with raised floor and should be water tight.

6) REINFORCEMENT

All steel bars, sections, plates and other miscellaneous steel materials, etc. shall be free from loose mill scales, rust as well as oil, mud, paint or other coatings. the materials, construction, specifications such as dimensions. Shape. Weight. Tolerances, testing etc, for all materials covered under this section. shall conform to respective IS code.

Steel reinforcement shall be stored in a way as to prevent distortion and corrosion of bars of different classification, sizes and lengths shall be stored separately to facilitate issues in such sizes and lengths as to minimize wastage in cutting from standard lengths.

High strength deformed (HSD) steel bars of minimum grade Fe500. Conforming to IS: -1786 shall be used.

PREFERABLE BRAND NAME OF STEEL COMPANEY-SAIL/TATA.

7) STONE CHIPS

Stone chips shall be hard, dense, strong, sound, and durable. Clean and uniform in color, they shall also be free from veins. Adherent coatings. Injurious amounts of alkalis, vegetable matters and other deleterious substance such as iron pyrites. Cold, lignite, mica, sea shells etc. as far as possible stones from one single quarry shall be used for anyone work. The strength of stones should be adequate to carry, the imposed load and shall meet all the requirements of relevant IS Code, taking into accounts the appreciate crushing strength of stone and type of the mortar used. The percentage of water absorption, when tested in accordance with IS: 1124 shall not exceed 5%.

8) COARSE SAND

Shall be either river sand or pit-sand, clean, sharp, strong, angular and composed of hard siliceous materials. It shall be approved by SAMEER. The sand shall conform to relevant IS code (IS: 383). Fineness modulus shall not be less than 2.5. The maximum quantity of silt shall not exceed 8%.

i) FINE SAND

This shall be natural river sand. Fineness modules shall not be less than 1.0. The maximum quantity of silt shall not exceed 8%. The sand shall conform to relevant IS specification (IS: 383).

9) BRICKS

Bricks for masonry work shall conform to IS: 1077- specification for common burnt clay building bricks and shall be of class 5.0 (with minimum compressive strength of 5.0 N/Sq mm).

Physical requirements, quality, dimension. Tolerances etc. of common burnt clay building bricks shall conform to the requirements of IS: 1077. Bricks shall be hand- modular or machine -molded and shall be made from suitable soils. The brick shall have smooth rectangular faces with sharp corners and shall be well burnt, sound, hard, tough and uniform in color. These shall be free from cracks, chips, flaws, stone or lumps of any kind. Testing of the bricks shall be done as per IS: 5454 and IS: 3495. Water absorption shall not be more than 20% by its dry weight when soaked in cold water for 24 hours .

10) ADMIXTURES

General requirements for admixtures.

All concrete Admixtures shall comply with the following Indian standards

Specification for integral cements water proofing compounds	IS:2645
Specification for other admixtures for concrete	IS:9103

in case of non-availability of any IS code for testing and acceptability criteria. Relevant American/ British or German code shall be applicable.

No admixture shall impair the durability of the concrete nor combine with the ingredients to form harmful compound nor increase the risk of corrosion of reinforcement. Use of admixture shall not reduce the dry density of concrete. Once the proportion of admixtures have been. Established, strict check shall be maintained not to alter the proportion of ingredients such as water- cement ratio of the design mix during execution. The chloride contains in admixtures shall not exceed 2% by mass of the admixture or 0.03% by mass of the cement.

PREFERABLE BRAND NAME OF BUILDING CHEMICAL COMPANNEY-SIKA/FOSROC/Dr. FIXIT/CHOKSEY.

11) WATER PROOFING COMPOUNDS

The polymer modified, flexible cementitious negative side waterproofing coating with elastic waterproofing polymers on interior wall plaster surface in three coats @14.35 kg /10 sqm. one coat of self-priming of cementitious waterproofing polymer (dilution with water in the ratio of 1:1) and two coats of cementitious waterproofing polymer (dilution with water in the ratio of 3:1) after scrapping and properly cleaning the surface to remove pre-existing paint film & loose particles till plaster is visible, complete in all respect as per the direction of Engineer-in-Charge.

PREFERABLE BRAND NAME OF BUILDING WATER PROOFING COMPOUNDS COMPANNEY-SIKA/FOSROC/Dr. FIXIT/CHOKSEY.

12) POLY SULPHIDE SEALANTS

All Polysulphide sealants shall conform to IS: 12118. Test conditions and requirements shall be as given in the above reference IS code and approved by SAMEER.

13) SANITARY & PLUMBING WORK

I) All **SANITARY & PLUMBING** Item including C.P.V.C pipes shall conform to the requirements of IS:4985 of several dia, pipes (medium density) conforming ASTM D- 1785 thread properly With all necessary accessories, specially (Socket, bend, tee, union, elbow, long Screw, reducing socket, including

Jointing materials are of Best quality as specified and approved by SAMEER, the pipe shall be provided complete with necessary clamps, connections, bends, tees, other accessories (as per approved manufactures specifications) and shall be jointed with approved quality bonding solution. Embedded rain water pipe shall be suitably embedded/ encased in masonry/ cement concrete (M20) with nominal reinforcement. Embedding within RCC should be avoided as far as -practicable.

PREFERABLE BRAND NAME OF C.P.V.C PIPES COMPANEY-SUPREME/ ORI-PLAST, AND
SANITARY FITTINGS COMPANEY -
HINDWARE/PARRYWARE/JAGUAR/JOHNSON/NEYCR/ESCO.

14) WOOD/TIMBER

Wood recommended from platform of cold vessels or below cold vessels/ exchangers shall be of group-a, grade-1, and shall have safe permissible stress of 7 MPa in compression, perpendicular to grains on outside location as per IS:3629. Timber required to be used for form work shall be fairly dry before use. It should maintain its shape during the use and even when it comes into contact with moisture from the concrete. Strength of wood/ timber shall be as per the requirements of IS: 4082.]

15) TECHNICAL SPECIFICATION OF REPAINTING & RESTORATION OF CIVIL WORKS

a. STRUCTURAL SUPPORT:

Providing appropriate & safe structural support in and around distress zone before taking up chipping or restoration work by using Sal-Ballah, heavy duty collapsible props or steel pipes as deemed necessary to ensure safety of the structure, under safe working condition as per approval of SAMEER.

b. CHIPPING & REMOVAL

Chipping and removal of damaged deteriorated, unbounded, spalled and unserviceable plaster and concrete and exposing the firm sound surface, including necessary staging and scaffolding.

c. CLEANING & SURFACE PREPARATION

Cleaning & preparation of the surface by mechanical means using powdered sand or high-pressure water jet and wire brushing to expose firm, sound substrate inclusive of necessary staging and scaffolding as directed by SAMEER.

d. REINFORCED CEMENT CONCRETE WORK

General

Reinforced cement concrete work may be cast-in-situ or precast as directed. Reinforced cement concrete work shall comprise of the following which may be paid separately or collectively as per the deception of the item of the work (a) form work (b) reinforcement (c) concrete (d) plastering or other finishing on concrete surface. All concrete works shall be carried out as per the provisions of IS: 456, IS: 3370, IS: 2974, and other relevant IS codes. concrete mix proportioning and design mix sampling and strength test of concrete, production and control of concrete, tolerances and placing of reinforcement and for cover, transporting, placing, compacting and curing etc, inspection and testing of structure shall be specified in IS: 456.as directed by SAMEER. Minimum strength of R.C.C. should be 20 N/Sq. mm, Minimum mix for cement, sand, plastering on wall and that on concrete surface 1:4.

The damp proof course shall be laid in two layers of equal thickness.

From work and stripping of form work shall as per the provision of IS: 456.

Assembly of reinforcement in RCC structure shall con form to IS: 456.

All masonry works shall be caried out as per the provisions of IS: 1597/2212/4326 and other relevant IS codes. Fabrication of structural steel work shall be carried out as per the provisions of IS: 800/801/802/806 and other relevant IS codes. Fabricator shall do cleaning, straightening, cutting,

bending, holding, bolting, welding marking, assembling, erecting, inspecting and testing etc. welding procedure and welder qualification shall be as per IS :800 and / or referred IS codes only.

e. TILES FINISHING

f. MARBLE, GRANITE

MATERIALS

A) MARBLE, GRANITE slabs shall be 15 to 20mm thick and grade- 1 as specified. the MARBLE/ GRANITE form with the slabs are made shall be of selected quality, hard, sound, dense, homogenous in texture, free from cracks, decay, weathering and flakes. the samples of marble stone slabs shall be got approved from SAMEER. The slabs shall be machine cut to the requisite dimensions
PREFERABLE BRAND NAME OF TILES COMPANY-JOHNSON/KAJARIA.

g. PAINT:

After the selection of Paints quality, types a standard Brand to be choice and specification is as Manufacturer's specification.

PREFERABLE BRAND NAME OF PAINT COMPANY-I.C.I/ASIANPAINTS/BERGER.INDIGO
FLOOR PAINT **(BEST QUALITY TOP GRADE)**

PREFERABLE BRAND NAME OF PUTTY COMPANY-JK/BIRLA/ASIAN WALL PUTTY

h. EXTRA ITEM /SUBSTITUTED ITEMS

PAYMENT OF NON-SCHEDULED ITEMS: Payment will be made for various items as per existing CPWD/ PWD (state) rate. If not available in CPWD/ PWD payment will be made based on prevailing market rate with submission of rate analysis and admitted by SAMEER before execution of work.

FORM OF TENDER

(To be filled up the form by the tenderer with sign and stamp in their Letter Head and to be submitted along with the **Financial Bid**)

To
The Officer-In-Charge
SAMEER Kolkata Centre
Salt Lake, Kolkata

Date:

Dear Sir,

I/We, _____ Son/Daughter of Sri _____
Proprietor/Partner/CEO/MD/Director of M/s. _____ of (Address)

_____ having examined the site of works, carefully read and understood the Specifications, General Conditions of Contract and Conditions of the Tender, hereby tender and undertake to execute and complete all the works required to be performed in accordance with the schedule of quantities, specifications and General Terms and Conditions of Contract. THE TOTAL AMOUNT PUT TO TENDER =Rs. _____ (Rupees _____)

I also declare that the information / documents furnished along with the application and tender are true and authentic to the best of my knowledge and belief. I am well aware of the fact that furnishing of any false information / fabricated document would lead to rejection of my tender / termination of contract at any stage besides liabilities towards prosecution under appropriate law. Each page of the tender document and papers submitted by my Company are authenticated, sealed and signed, and I take full responsibility for the entire documents submitted with this tender.

Signature of the Tenderer / Authorised person
(Seal of the Tenderer)

Name of the Tenderer _____ (in Block letters)

Signature: _____

Name: _____

Address :(in block letters) _____

ANNEXURE

SCHEDULE OF QUANTITIES -SAMEER- SECTOR-V

Brief Description of work: - Up-gradation of Non-Residential building at SAMEER Kolkata Centre, Sector- V during 2023-24.
S.H: - Renovation Various Toilet (Gr floor Gent's toilet- Corridor, Gr. Floor Gent's toilet- back side, 1st floor ladies toilet – back side & 1st gent's toilet back side), New shed, Extension of Dining, Extension of Basin, Renovation Canteen & Electric Sub-station work etc.

SLNo	Description	Qty	Unit	To be filled up by the bidders	
				Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.				
1.1	All kinds of soil.	1.94	cum		
2	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	8.13	cum		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
3.1	1:3:6 (1 Cement : 3 coarse sand (zone-III) : 6 graded stone aggregate 20 mm nominal size).	5.74	cum		
4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :				
4.1	1:1.5:3 (1 cement : 1.5 coarse sand (zone-III): 3 graded stone aggregate 20 mm nominal size).	8.06	cum		
5	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size).	0.39	cum		
6	Centering and shuttering including strutting, propping etc. and removal of form for all heights :				
6.1	Lintels, beams, plinth beams, girders, bressumers and cantilevers	11.85	sqm		
6.2	Columns, Pillars, Piers, Abutments, Posts and Struts	2.40	sqm		
7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.				
7.1	Thermo-Mechanically Treated bars of grade Fe-500D or more.	967.20	Kg		
8	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level.				
8.1	Thermo-Mechanically Treated bars of grade Fe-500 D or more.	37.95	Kg		

SLNo	Description	Qty	Unit	Rate	Amount
9	Providing and fixing of expansion joint system related with floor location as per drawings and direction of Engineer-In-Charge. The joints system will be of extruded aluminum base members, self aligning / self centering arrangement and support plates etc. as per ASTM B221-02. The system shall be such that it provides floor to floor /floor to wall expansion control system for various vertical locations in load application areas that accommodates multi directional seismic movement without stress to it's components. System shall consist of metal profiles with a universal aluminum base member designed to accommodate various project conditions and finish floor treatments. The cover plate shall be designed of width and thickness required to satisfy projects movement and loading requirements and secured to base members by utilizing manufacturer's pre-engineered self-centering arrangement that freely rotates / moves in all directions. The Self - centering arrangement shall exhibit circular sphere ends that lock and slide inside the corresponding aluminum extrusion cavity to allow freedom of movement and flexure in all directions including vertical displacement. Provision of Moisture Barrier Membrane in the Joint System to have watertight joint is mandatory requirement all as per the manufactures design and as approved by Engineer -in- Charge. (Material shall conform to ASTM 6063).				
9.1	Floor Joint of 100 mm gap	7.40	metre		
10	Providing and fixing of expansion joint system related with wall joint (internal/ external) location as per drawings and direction of Engineer-In- Charge. The joints shall be of extruded aluminum base members, self aligning / centering arrangement and support plates as per ASTM B221- 02. The material shall be such that it provides an Expansion Joints System suitable for vertical wall to wall/ wall to corner application, both new and existing construction in office Buildings & complexes with no slipping down tendency amongst the components of the Joint System. The Joint System shall utilize light weight aluminum profiles exhibiting minimal exposed aluminum surfaces mechanically snap locking the multicellular to facilitate movement. (Material shall conform to ASTM 6063.)				
10.1	Wall Joint of 100 mm gap	12.00	metre	4835.5	

SLNo	Description	Qty	Unit	Rate	Amount
11	Providing and fixing of expansion joint system of approved make and manufacture for various roof locations as per approved drawings and direction of Engineer-In-Charge. The joints shall be of extruded aluminum base members with, self aligning and self centering arrangement support plates as per ASTM B221-02. The system shall be such that it provides water tight roof to roof /roof to corner joint cover expansion control system that is capable of accommodating multidirectional seismic movement without stress to its components. System shall consist of metal profile that incorporates a universal aluminum base member designed to accommodate various project conditions and roof treatments. The cover plate shall be designed of width and thickness required to satisfy movement and loading requirements and secured to base members by utilizing manufacturer's pre-engineered self-centering arrangement that freely rotates / moves in all directions. The Self centering arrangement shall exhibit circular sphere ends that lock and slide inside the corresponding aluminum extrusion cavity to allow freedom of movement and flexure in all directions including vertical displacement. The Joint System shall resists damage or deterioration from the impact of falling ice, exposure to UV, airborne contaminants and occasional foot traffic from maintenance personnel. Provision of Moisture Barrier Membrane in the Joint System to have water tight joint is mandatory requirement. (Material shall confirm to ASTM 6063.)				
11.1	Roof Joint of 100 mm gap	7.90	metre		
12	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:				
12.1	Cement mortar 1:4 (1 cement : 4 coarse sand)	3.49	cum		
13	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :				
13.1	Cement mortar 1:4 (1 cement : 4 coarse sand)	5.48	cum		
14	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	151.16	Sqm		
15	12 mm thick pre-laminated particle board (decorative lamination on both sides) grade -1, medium density flat pressed, three layer particle board FPT- I or graded wood particle board FPT- I, conforming to IS : 3087, bonded with BWP type synthetic resin adhesive as per IS : 848 and pre-laminated conforming to IS : 12823, Grade 1, Type - II marked :	23.10	sqm		

SLNo	Description	Qty	Unit	Rate	Amount
16	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters.				
16.1	35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	1.72	sqm		
17	Extra for providing lipping with 2nd class teak wood battens 25 mm minimum depth on all edges of flush door shutters (over all area of door shutter to be measured).	1.72	sqm		
18	Providing and fixing mild steel round holding down bolts with nuts and washer plates complete.	4.26	Kg		
19	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.				
19.1	Electric resistance or induction butt welded tubes	2080.17	kg		
20	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete.				
20.1	Size of Tile 600x600 mm	21.07	sqm		
21	Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only . Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily				
21.1	Glazed Vitrified tiles Matt/Antiskid finish of size				
21.1	Size of Tile 600 x 600 mm	18.68	Sqm		
21.1.2	Size of Tile 1000 x 1000 mm	67.28	Sqm		

SLNo	Description	Qty	Unit	Rate	Amount
22	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge				
2.1	Polished Granite stone slab colour of Black, Cherry/Ruby Red or equivalent	29.47	sqm		
23	Making khurras 45x45 cm with average minimum thickness of 5 cm cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate of 20 mm nominal size) over P.V.C. sheet 1 m x1 m x 400 micron, finished with 12 mm cement plaster 1:3 (1 cement : 3 coarse sand) and a coat of neat cement, rounding the edges and making and finishing the outlet complete.	10.00	each		
23	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.				
23.1	110 mm diameter	18.00	metre		
24	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer- in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	32.68	sqm		
25	Providing and fixing pre-coated galvanised steel sheet roofing accessories 0.50 mm (+ 0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete :				
25.1	Gutter .(600 mm over all girth)	4.50	metre		

SLNo	Description	Qty	Unit	Rate	Amount
26	Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on interlocking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge.				
26.1	GI Metal Ceiling Lay in plain Tegular edge Global white color tiles of size 595x595 mm, and 0.5 mm thick with 8 mm drop; made of G I sheet having galvanizing of 100 gms/sqm (both sides inclusive) and electro statically polyester powder coated of thickness 60 microns (minimum), including factory painted after bending.	83.45	sqm		
27	12 mm cement plaster of mix :				
27.1	1:4 (1 cement: 4 fine sand)	191.97	sqm		
28	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface :				
28.1	Water thinnable cement primer	317.61	Sqm		
29	Finishing walls with Acrylic Smooth exterior paint of required shade :				
29.1	New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	134.40	sqm		

SLNo	Description	Qty	Unit	Rate	Amount
30	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade :				
30.1	Two or more coats on new work	317.61	Sqm		
31	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :				
31.1	Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	108.08	sqm		
32	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	317.61	Sqm		
33	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per directions of Engineer-In-Charge.				
33.1	With cement mortar 1:4 (1cement: 4 coarse sand)	101.20	Sqm		
34	Dismantling W.C. Pan / urinal / wash basin of all sizes including disposal of dismantled materials i/c malba all complete as per directions of Engineer-in- Charge.	14.00	each		
35	Dismantling 15 to 40 mm dia G.I. pipe including stacking of dismantled pipes within 50 metres lead as per direction of Engineer- in-Charge. (a) Internal Work - Exposed on wall	37.70	metre		
36	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.				
36.1	Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	4.53	Cum.		
37	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.				
37.1	In cement mortar	8.56	cum		
38	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead :				
38.1	Of area 3 sq. metres and below	2.00	each		
39	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.				
39.1	For thickness of tiles 10 mm to 25 mm	131.99	Sqm		
40	Dismantling C.I. or asbestos rain water pipe with fittings and clamps including stacking the material within 50 metres lead :				
40.1	100 mm dia pipe	18.00	metre		
41	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	110.66	sqm		

SLNo	Description	Qty	Unit	Rate	Amount
42	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable surplus material and stacking of serviceable material with in 50 meters lead as directed by Engineer-in-charge.	60.48	sqm		
43	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required :				
43.1	W.C. pan with ISI marked white solid plastic seat and lid	3.00	each		
44	Providing and fixing wash basin with C.I. brackets, 15 mm dia CP Brass single hole basin mixer of approved quality and make, including painting of fittings and brackets, cutting and making good the walls wherever required:- (a) White Vitreous China Wash basin size 550x400 mm with a 15 mm CP Brass single hole basin mixer	3.00	each		
45	Providing and fixing 600x120x5 mm glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm long screws, rawl plugs etc., complete.	3.00	each		
46	Providing and fixing toilet paper holder :				
46.1	C.P. brass	3.00	each		
47	Providing and fixing soil, waste and vent pipes :				
47.1	100 mm dia				
47.1.1	Centrifugally cast (spun) iron socket & spigot (S&S) pipe as per IS: 3989	15.40	metre		
48	Providing and filling the joints with spun yarn, cement slurry and cement mortar 1:2 (1 cement : 2 fine sand) in S.C.I./ C.I. Pipes :				
48.1	100 mm dia pipe	38.00	each		
49	Providing and fixing M.S. holder-bat clamps of approved design to Sand Cast iron/cast iron (spun) pipe embedded in and including cement concrete blocks 10x10x10 cm of 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), including cost of cutting holes and making good the walls etc. :				
49.1	For 100 mm dia pipe	9.00	each		
50	Providing and fixing plain bend of required degree.				
50.1	100 mm dia				
50.1.1	Sand cast iron S&S as per IS : 3989	9.00	each		
51	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors :				
51.1	100 mm inlet and 100 mm outlet				
51.1.1	Sand cast iron S&S as per IS: 3989	9.00	each		

SLNo	Description	Qty	Unit	Rate	Amount
52	Providing and fixing PTMT liquid soap container 109 mm wide, 125 mm high and 112 mm distance from wall of standard shape with bracket of the same materials with snap fittings of approved quality and colour, weighing not less than 105 gms.	7.00	each		
53	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour.				
53.1	600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm, weighing not less than 190 gms.	3.00	each		
54	Providing and fixing PTMT 15 mm Urinal spreader size 95x69x100 mm with 1/2" BSP thread and shapes, weighing not less than 60 gms.	4.00	each		
55	Providing and fixing M.S. holder bat clamp of approved design to sand cast iron/ cast iron (spun) pipes comprising of M.S. flat brackets made of 50x5 mm flat of specified shape, projecting 75 mm outside the wall surface and fixed on wall with 4nos, 6mm dia expansion hold fasteners, including drilling necessary holes in brick wall/ CC/ RCC surface and the cost of bolts etc. The pipes shall be fixed to the already fixed brackets with the help of 30 mm x1.6 mm galvanised M.S. flats of specified shape and of total length 420 mm and shall be fixed with M.S. nuts, bolts, & washers of size 25x6 mm, one bolts on each side of the pipe.				
55.1	Total bracket length 580 mm of approved shape and design (for single 100 mm dia pipe)	12.00	each		
56	Providing & fixing white vitreous china water less urinal of size 600 x 330 x 315 mm having antibacterial /germs free ceramic surface, fixed with cartridge having debris catcher and hygiene seal.	4.00	each		
57	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc.				
57.1	20 mm nominal outer dia Pipes	23.65	metre		
57.2	25 mm nominal outer dia Pipes	13.10	metre		
57.3	32 mm nominal outer dia Pipes	21.10	metre		
58	Providing and fixing uplasticised PVC connection pipe with brass unions :				
58.1	45 cm length				
58.1.1	15 mm nominal bore	14.00	each		
59	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931				
59.1	15mm nominal bore	14.00	each		
60	Providing and fixing PTMT grating of approved quality and colour.				

SLNo	Description	Qty	Unit	Rate	Amount
60.1	Circular type				
60.1.1	100 mm nominal dia	13.00	each		
61	Providing and fixing PTMT soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm with concealed fitting arrangements, weighing not less than 106 gms.	7.00	each		
62	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item):				
62.1	With float glass panes of 4.0 mm thickness	7.01	sqm		
63	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :				
63.1	For fixed portion				
63.1.1	Powder coated aluminium (minimum thickness of powder coating 50 micron)	240.04	kg		
64	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately)				
64.1	Powder coated aluminium (minimum thickness of powder coating 50 micron)	23.63	kg		
65	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item):				
65.1	With float glass panes of 5.50 mm thickness	9.90	sqm		
66	Providing and fixing double action hydraulic floor spring of approved brand and manufacture conforming to IS : 6315, having brand logo embossed on the body / plate with double spring mechanism and door weight upto 125 kg, for doors, including cost of cutting floors, embedding in floors as required and making good the same matching to the existing floor finishing and cover plates with brass pivot and single piece M.S. sheet outer box with slide plate etc. complete as per the direction of Engineer-in-charge.				
66.1	With stainless steel cover plate minimum 1.25 mm thickness	1.00	each		

SLNo	Description	Qty	Unit	Rate	Amount
67	Providing and fixing aluminium round shape handle of outer dia 100 mm with SS screws etc. complete as per direction of Engineer-in- charge				
67.1	Anodized (AC 15) aluminium	1.00	each		
68	Providing, mixing and applying bonding coat of approved adhesive on chipped portion of RCC as per specifications and direction of Engineer-In-charge complete in all respect.				
68.1	SBR Polymer (@10% of cement weight) modified cementitious bond coat @2.2 kg cement per sqm of surface area mixed with specified proportion of approved polymer	18.53	Sqm.		
69	Providing, mixing and applying SBR polymer (of approved make) modified Cement mortar in proportion of 1:4 (1 cement: 4 graded coarse sand with polymer minimum 2% by wt. of cement used) as per specifications and directions of Engineer-in-charge. Note: Measurement and payment: The pre-measurement of thickness shall be done just after the surface preparation is completed and Payment under this item shall be made only after proper wet curing has been done and surface has been satisfactorily evaluated by sounding / tapping with a blunt metal instrument and/or the 75mm size cube crushing strength at the end of 28 days to be not less than 30 N/ mm ²).				
69.1	25 mm average thickness in 2 layers.	18.53	Sqm.		
70	Providing and fixing Curved shaped urinal partition with frosted glass approved brand of Jaquar Code-Model No. 1810-UC / 1110UC OR JSE-CHR-110UC450X (CERA / Jaquar / Hindware / Marc) or equivalent all complete as per direction of the Engineer – in – Charge.	6.00	each		
71	Providing and fixing Double Arm Wall Mounted Reversible Plain / Magnifying (X3) Pivotal Mirror approved brand of Jaquar Code- ACN-1193N (CERA / Jaquar / Hindware / Marc) or equivalent all complete as per direction of the Engineer – in – Charge.	7.00	each		
72	Providing and fixing Bottle Trap 32mm Size with 250mm & 190mm Long Wall Connection Pipes & Wall Flange approved brand of Jaquar Code- ALD-769L250x190 (CERA / Jaquar / Hindware / Marc) or equivalent all complete as per direction of the Engineer – in – Charge.	11.00	each		
73	Providing and fixing 2-way Bib Cock with Wall Flange approved brand of Jaquar Code- COP-041PM (CERA / Jaquar / Hindware / Marc) or equivalent all complete as per direction of the Engineer – in – Charge.	3.00	each		
74	Providing and fixing Hand Shower (Health Faucet) with 8mm Dia, 1 Meter Long Flexible Tube & Wall Hook approved brand of Jaquar Code- ALD-573 (CERA / Jaquar / Hindware / Marc) or equivalent all complete as per direction of the Engineer – in – Charge.	3.00	each		

SLNo	Description	Qty	Unit	Rate	Amount
75	Providing and fixing Counter Top Basin, Size: 500x435x180 mm approved brand of Jaquar Code- KUS-WHT-35601 (CERA / Jaquar / Hindware / Marc) or equivalent all complete as per direction of the Engineer – in – Charge.	4.00	each		
76	Providing and fixing Pillar Cock with Extension Body approved brand of Jaquar Code-COP-021PM (CERA / Jaquar / Hindware / Marc) or equivalent all complete as per direction of the Engineer – in – Charge.	4.00	each		
	Sub Total				
	Add, GST				
	Total				